

|                           |                                                                                     |
|---------------------------|-------------------------------------------------------------------------------------|
| Test Report N° 20994-1-TR |  |
| Colombia                  | Page 1 of 12                                                                        |

#### TESTING LABORATORY

Name ..... : Certification Entity for Renewable Energies, S.L.  
(CERE Testing Laboratory)  
Address ..... : C/ Monturiol 15. 28906. Getafe - Madrid - España.  
Conducted (tested) by ..... : Otto Intriago  
Test Date ..... : 28/04/2021; 12/11/2021  
Issue Date ..... : 23/03/2022

#### SITE TEST

Name ..... : Certification Entity for Renewable Energies, S.L.  
Address ..... : C/ Monturiol 15. 28906. Getafe - Madrid - España.

#### LICENCE HOLDER

Name ..... : Huawei Technologies Colombia S.A.S.  
Address ..... : Cra 68ª No. 24B-10. Plaza Claro, Tower 2, 10th floor.

#### APPLICANT

Name ..... : Huawei Technologies Colombia S.A.S.  
Address ..... : Cra 68ª No. 24B-10. Plaza Claro, Tower 2, 10th floor.

#### APPLIED SPECIFICATIONS

This protocol is based on the standard ..... : **Comisión de Regulación de Energía y Gas: Resolución No. 148 de 2021.** Por la cual se adiciona un Capítulo Transitorio al Anexo General del Reglamento de Distribución contenido en la Resolución CREG 070 de 1998, para permitir la conexión y operación de plantas solares fotovoltaicas y eólicas en el SDL con capacidad efectiva neta o potencia máxima declarada igual o mayor a 5 MW y se dictan otras disposiciones.

- Clause: 11.2.4

#### SAMPLES CHARACTERISTICS

Apparatus type/ Installation ..... : Three-Phase Solar Inverter

Manufacturer/ Supplier/ Installer ..... : Huawei

Trademark ..... :   
HUAWEI

Models ..... : SUN2000-185KTL-H1

Serial Number ..... : 6T1979046065 Y

Firmware version ..... : V300R001

Rated Characteristics ..... : Pn: 175,00 kW, Pmax: 185,00 kW, 800VAC, 60Hz & 126,30A  
See point 2 of this test report, "General Information"

|                                     |                                       |
|-------------------------------------|---------------------------------------|
| Performed by:                       | Approved by:                          |
| Otto Intriago<br>(Testing Engineer) | Alberto Martín<br>(Technical Manager) |

|                           |                                                                                     |
|---------------------------|-------------------------------------------------------------------------------------|
| Test Report N° 20994-1-TR |  |
| Colombia                  | Page 2 of 12                                                                        |

## INDEX

|                                                                                |           |
|--------------------------------------------------------------------------------|-----------|
| <b>1. SCOPE .....</b>                                                          | <b>3</b>  |
| <b>2. GENERAL INFORMATION.....</b>                                             | <b>3</b>  |
| 2.1. Tested item: Particular characteristics. ....                             | 3         |
| 2.2. Rating plate: .....                                                       | 3         |
| 2.3. Summary of inspection and test results: .....                             | 4         |
| <b>3. TEST EQUIPMENT LIST / MEASUREMENT UNCERTAINTY &amp; TEST SETUP .....</b> | <b>5</b>  |
| 3.1. Test Equipment List: .....                                                | 5         |
| 3.2. Measurement Uncertainties: .....                                          | 5         |
| 3.3. Test set up: .....                                                        | 6         |
| <b>4. RESUME OF TEST RESULTS.....</b>                                          | <b>6</b>  |
| 4.1. Chapter of the Standard .....                                             | 6         |
| <b>5. TEST RESULTS.....</b>                                                    | <b>7</b>  |
| 5.1. LVRT & HVRT .....                                                         | 7         |
| <b>6. PICTURES .....</b>                                                       | <b>11</b> |
| <b>7. ELECTRICAL SCHEME .....</b>                                              | <b>12</b> |

## 1. SCOPE

**Certification Entity for Renewable Energies, S.L.** (CERE Testing Laboratory) has been contracted by **Huawei Technologies Colombia S.A.S.** in order to perform the testing according to the network connection standards specified in page 1 "Applied specifications".

## 2. GENERAL INFORMATION

### 2.1. Tested item: Particular characteristics.

|                                                  |                             |
|--------------------------------------------------|-----------------------------|
| Input .....                                      | 500 – 1500 Vdc, max 1500Vdc |
| Output .....                                     | 800 Vac,                    |
| Class of protection against electric shock ..... | Class I                     |
| Degree of protection against moisture .....      | IP66                        |
| Type of connection to the main supply .....      | 3W + PE                     |
| Cooling group .....                              | Smart Air Cooling           |
| Modular .....                                    | No                          |
| Internal Transformer .....                       | No                          |
| Climatic Condition .....                         | -25 °C~ 60 °C               |

### 2.2. Rating plate:



|                           |                                                                                     |
|---------------------------|-------------------------------------------------------------------------------------|
| Test Report N° 20994-1-TR |  |
| Colombia                  | Page 4 of 12                                                                        |

### 2.3. Summary of inspection and test results:

All the tests and checks have been performed in accordance with the reference Standard as specified previously.

The results obtained apply only to the particular sample tested that is the subject of the present test report. The most unfavourable result values of the verifications and tests performed are contained herein.

Throughout this report a comma is used as the decimal separator.

| Version | Modifications  |
|---------|----------------|
| 0       | Initial report |

The present test report cannot be copied partially without the express written consent of the Testing Laboratory.

Two setups were used to perform the tests:

- Setup 1 was used to perform LVRT (28/04/2021)
- Setup 2 was used to perform HVRT (12/11/2021)

NOTE: Accredited activities can be found into the accreditation scope.

#### WEATHER CONDITIONS

Temperature: 23,00 - 24,60 °C

Humidity: 25,40 – 35,20 %HR

|                           |                                                                                     |
|---------------------------|-------------------------------------------------------------------------------------|
| Test Report N° 20994-1-TR |  |
| Colombia                  | Page 5 of 12                                                                        |

### 3. TEST EQUIPMENT LIST / MEASUREMENT UNCERTAINTY & TEST SETUP

#### 3.1. Test Equipment List:

##### CERE'S EQUIPMENT LIST

###### Set up 1

| No. | TEST EQUIPMENT    | MANUFACTURER / MODEL | CODE N°                          | CALIBRATION DATE |            |
|-----|-------------------|----------------------|----------------------------------|------------------|------------|
|     |                   |                      |                                  | LAST             | DUE        |
| 1   | Power Analyzer    | ZES ZIMMER / LMG500  | CERE_001                         | 13/05/2020       | 13/05/2022 |
| 2   | AC Current Sensor | ZES ZIMMER / L45-Z10 | CERE_002<br>CERE_003<br>CERE_004 | 13/05/2020       | 13/05/2022 |
| 3   | Multimeter        | FLUKE / 179          | CERE_008                         | 26/10/2020       | 26/10/2021 |
| 4   | Weather station   | VELLEMAN / WS8472    | CERE_012                         | 22/10/2020       | 22/10/2021 |

###### Set up 2

| No. | TEST EQUIPMENT    | MANUFACTURER / MODEL | CODE N°                          | CALIBRATION DATE |            |
|-----|-------------------|----------------------|----------------------------------|------------------|------------|
|     |                   |                      |                                  | LAST             | DUE        |
| 1   | Power Analyzer    | Dewesoft / SIRIUS    | CERE_180                         | 18/05/2021       | 18/05/2023 |
| 2   | AC Current Sensor | LEM / IT 700-S       | CERE_212<br>CERE_213<br>CERE_214 | 13/05/2020       | 13/05/2022 |
| 3   | Multimeter        | FLUKE / 179          | CERE_008                         | 02/11/2021       | 02/11/2022 |
| 4   | Weather station   | VELLEMAN / WS8472    | CERE_012                         | 22/10/2021       | 22/10/2022 |

#### 3.2. Measurement Uncertainties:


##### Setup 1

|                                   |         |
|-----------------------------------|---------|
| Voltage measurement uncertainty   | ±0,46 % |
| Current measurement uncertainty   | ±0,78 % |
| Power measurement uncertainty     | ±0,38 % |
| Frequency measurement uncertainty | ±0,12 % |

##### Setup 2

|                                   |         |
|-----------------------------------|---------|
| Voltage measurement uncertainty   | ±0,26 % |
| Current measurement uncertainty   | ±0,29 % |
| Power measurement uncertainty     | ±0,26 % |
| Frequency measurement uncertainty | ±0,12 % |

### 3.3. Test set up:



Current sensors and voltage probes have been connected to the output and/or input of equipment under test (EUT) according to each test requirement.

All the tests described in the following pages have been performed using this specified test setup.


## 4. RESUME OF TEST RESULTS

### 4.1. Chapter of the Standard


| Test N° | Test Description: | Standard Reference                                                  |
|---------|-------------------|---------------------------------------------------------------------|
| 5.1     | LVRT & HVRT       | 11.2.4 (Características de depresiones de tensión y sobretensiones) |

## 5. TEST RESULTS

### 5.1. LVRT & HVRT



**Note:** LVRT tests performed to match with CREG 148:2021 and CREG 060:2019 requirements, as shown in the picture below.



|                           |                                                                                     |
|---------------------------|-------------------------------------------------------------------------------------|
| Test Report N° 20994-1-TR |  |
| Colombia                  | Page 8 of 12                                                                        |



| LVRT                                |         |                           |                      |                   |                    |            |                    |                     |                        |
|-------------------------------------|---------|---------------------------|----------------------|-------------------|--------------------|------------|--------------------|---------------------|------------------------|
| Fault type                          | Load    | Voltage Level desired (%) | Voltage measured (%) | Time minimum (ms) | Time measured (ms) | Kf desired | Iqpos measured (%) | Iq neg measured (%) | Iq injection time (ms) |
| <b>800 V (or reference V) 60 Hz</b> |         |                           |                      |                   |                    |            |                    |                     |                        |
| 3P                                  | 100%    | 0 ± 5%                    | 5,21%*               | 200,00            | 240,00             | 2          | 94,84%             | 0,11%               | 20,00                  |
| 1P                                  | 100%    | 0 ± 5%                    | 7,82%*               | 200,00            | 233,80             | 2          | 51,68 %            | 48,79 %             | 20,00                  |
| 3P                                  | No Load | 0 ± 5%                    | 2,16%                | 200,00            | 237,00             | --         | --                 | --                  | -                      |
| 1P                                  | No Load | 0 ± 5%                    | 3,63%                | 200,00            | 244,00             | --         | --                 | --                  | -                      |
| 3P                                  | 100%    | 20 ±5%                    | 20,47%               | 700,00            | 900,00             | 2          | 100,71%            | 0,12%               | 40,00                  |
| 1P                                  | 100%    | 20 ±5%                    | 73,46%               | 700,00            | 880,00             | 2          | 51,39%             | 50,30%              | 20,00                  |
| 3P                                  | 100%    | 50 ±5%                    | 50,71%               | 1300,00           | 2004,00            | 2          | 93,33%             | -0,14%              | 20,00                  |
| 1P                                  | 100%    | 50 ±5%                    | 84,77%               | 1300,00           | 1870,40            | 2          | 32,77 %            | 31,64 %             | 40,00                  |
| 3P                                  | 100%    | 85 ± 5%                   | 84,93%               | 2000,00           | 3022,70            | 2          | 30,04%             | 0,12%               | 40,00                  |
| 1P                                  | 100%    | 85 ± 5%                   | 94,99%               | 2000,00           | 3006,00            | 2          | 0,17%              | 0,97%               | 40,00                  |

(\*) Voltage level above desired due to inverter's current injection. "No Load" tests performed to verify LVRT conditions.


**Note 3:** Minimum time interval between 2 consecutives LVRT of 300 ms, by manufacturer declaration (Certificate no. 19-0650\_0 based on FGW TR 4 Rev.09).

| HVRT                                |      |                           |                      |                   |                    |            |                    |                     |                        |
|-------------------------------------|------|---------------------------|----------------------|-------------------|--------------------|------------|--------------------|---------------------|------------------------|
| Fault type                          | Load | Voltage Level desired (%) | Voltage measured (%) | Time minimum (ms) | Time measured (ms) | Kf desired | Iqpos measured (%) | Iq neg measured (%) | Iq injection time (ms) |
| <b>800 V (or reference V) 60 Hz</b> |      |                           |                      |                   |                    |            |                    |                     |                        |
| 3P                                  | 100% | 120 ± 5%                  | 119,44%              | 2000,00           | 2014,65            | 1,77       | -32,08%            | 0,12%               | 40,00                  |

**Note 4:** Configurable reactive power injection within the voltage tolerance, after fault recovery between 0s and 5s, by manufacturer declaration.

**Graphic-Fault type LVRT 3P-0,85****Graphic-Fault type LVRT 3P\_0,01**

### Graphic-Fault type HVRT



## 6. PICTURES



## 7. ELECTRICAL SCHEME

